THE CONNER GROUP

DPM2-40DP

DUR-A-LIFT PERSONNEL BUCKET

MAX. WORKING HEIGHT*	PLATFORM HEIGHT	MAX. SIDE REACH	BASKET CAPACITY
47 ft	40 ft	30 ft 3 in	600 lb

***47-ft maximum working height requires the optional 22-in basket elevator.**



Manufacturer series reference image; chassis and installed options vary.

PERSONNEL CONFIGURATION

- Double-person telescopic articulating lift
- 24 x 42-in basket; aluminum or fiberglass
- 180-degree basket rotation
- Hydraulic basket leveling
- Proportional controls; lower override
- Engine start/stop from basket
- Basket accessible from ground

INSULATION & OPTIONS

DPM2: insulated, Category C or D.
DPM2S: non-insulated alternative.
Basket elevator, outriggers, liners, tool circuits and DC backup are options.

MODEL SPECIFICATIONS

Height to platform bottom	40 ft
Maximum working height*	47 ft
Side reach	30 ft 3 in
Approx. stowed height	10 ft 6 in
Approx. lift weight	3,800 lb
Articulating arm travel	0 to 83 deg
Main boom travel	-29 to 70 deg
Extension travel	96 in
Basket capacity (DP)	600 lb
Basket rotation	180 degrees

Confirm rental-unit configuration and insulation rating. Specifications may vary with chassis and options.
Source: dur-a-lift.com/products/dpm2-dp-series/ and manufacturer DPM2 specifications table.