THE CONNER GROUP
AUGERS / BUCKETS / HD DRILLS / SPLICING / COW

WOMEN-OWNED
UTILITY BUSINESS

NEW EQUIPMENT SALES

VERSALIFT STP-36-NE CABLE PLACER

FORD F-550 REGULAR CAB 4x4 | NON-INSULATED



WORKING HEIGHT
40 ft 6 in

PLATFORM HEIGHT
35 ft 6 in

COMBINED LOAD LIMIT
350 lb maximum

CHASSIS GVWR
19,550 lb

CABLE PLACING & UTILITY CONSTRUCTION

AERIAL & CONTROLS

Non-insulated STP-36-NE aerial
370-degree non-continuous rotation
24 x 30 x 42-in steel-tube platform
Hinged door / hydraulic platform leveling
Single-stick 3-axis upper control
Wired handheld lower control
Two-speed boom controls / DC backup
2 GPM at 2,250 PSI / 6-gal reservoir
Cab-to-platform intercom
120V GFCI outlet / pneumatic circuit
2,000W inverter with auxiliary battery

CHASSIS & BODY

2026 Ford F-550 Regular Cab 4x4
6.7L Power Stroke diesel
10-speed automatic transmission
169-in wheelbase / 84-in cab-to-axle
B&G 132 x 94 x 40-in steel service body
30-in full-width tailshelf / curbside steps
PTO-driven hydraulic pump
4-corner LEDs / knuckle strobes
Combo pintle hitch / 7-pin receptacle
Aluminum ladder rack / rear torsion bar
Backup alarm / wheel chocks

350 lb maximum combined platform load plus cable download; cable download must not exceed 50 lb. Mobile operation maximum 2 mph. Final configuration, availability, tax and delivery confirmed with quotation.

CALL FOR PRICE