# GLADIATOR G60 HORIZONTAL DIRECTIONAL DRILL

**NEW EQUIPMENT SALES | UNDERGROUND CONSTRUCTION**




## DRILL PERFORMANCE

**THRUST / PULLBACK**
**62,946 lb**

**ROTARY TORQUE**
**9,219 ft-lb**

**ENGINE**
**202 hp Cummins**

**FLUID SYSTEM**
**125 gpm @ 1,080 psi**

## TECHNICAL SPECIFICATIONS

| | |
|---|---|
| **Pullback Speed** | 213 ft/min |
| **Rotation** | 220 rpm |
| **Entry Angle** | 21° |
| **Suggested Crossing** | Up to 1,312 ft |
| **Suggested Reaming** | Up to 39.37 in |
| **Rod Rack** | 40 rods |
| **Rod Size** | 2.87 in x 181 in |
| **Weight** | 25,353 lb |

## EQUIPMENT & SYSTEMS

**CONSTRUCTION**
Steel hood, rotating cab, rod-loader arms

**CARRIAGE SYSTEM**
Dual rack-and-pinion

**SYSTEMS**
Auto anchor, mud-flow adjustment, shut-off valves

**SAFETY**
Antifreeze tank, strike alert, seat sensor

**CONTROLS**
Wireless remote with hydraulic lockout shut-off

**DIMENSIONS: 283.46 in L × 89.37 in W × 94.48 in H**

Current OEM G60 specification reference. Crossing and reaming depend on ground conditions.

**EQUIPMENT SALES**

Confirm configuration, availability and delivery with quotation.

**CALL FOR PRICE**