SPLICE LAB PICKUP

SLP | SB-01 SERVICE CAPSULE

INTERIOR HEIGHT	WORKBENCH	MINIMUM BED	MINIMUM TRUCK
73 in	84 in	8 ft	3/4 ton



Illustrative jobsite setting. SpaceKap example; specifications describe the SB-01 rental configuration.



ILLUSTRATIVE JOBSITE SETTING

SpaceKap Diablo shown as an example. Specifications on this sheet describe the SB-01 rental configuration.

TRUCK, ACCESS & WORKSPACE

MINIMUM TRUCK	3/4-ton pickup
BED LENGTH	At least 8 ft
RENTAL CHASSIS	Ford, RAM or Chevrolet pickup
REAR DOORS	50/50 split
ACCESS	Grab handle for three-point rear access
CAPSULE	SB-01 full-size slip-in service capsule
INTERIOR HEIGHT	73 in
CABLE ACCESS	Custom rear cable-access door
WINDOW	Sliding window with screen
BACKUP CAMERA	Connects to factory system

INSIDE THE SLP CAPSULE

WORKBENCH, STORAGE & POWER



SpaceKap Diablo shown as an example. Specifications on this sheet describe the SB-01 rental configuration.

WORKSPACE & STORAGE

WORKBENCH	84-in. black-steel bench with shelf
POWER BAR	30-in. bar on bench backsplash
SHELVING	Four-tier 48-in. aluminum shelving; locking door and dividers
HOOKS	Two fixed hooks
LADDER RACK	External locking, side-mounted rack
GENERATOR BAY	Exterior locking door, heavy-duty slide-out tray and rain gutter

ELECTRICAL & CLIMATE

AIR CONDITIONING	Low-profile rooftop; 9,200 BTU/hr
DISTRIBUTION	120V system with dedicated A/C circuit
OUTLETS	Two duplex outlets, including one GFCI
AUTO-CHARGER	12VDC; powers 12VDC loads while generator runs
CAB CONTROLS	Wiring and switch panel

LIGHTING & ACCESSORIES

BENCH LIGHTING	Two 18-in. LED lights above workbench
BEACON	LED amber beacon light
WORK LAMP	High-output LED rear work lamp
ALARM	Carbon-monoxide alarm
CAMERA	Backup camera connects to factory system