JLG 600AJI / TCG INSULATED MANLIFT

46 KV CAT E ARTICULATING BOOM LIFT | READY TO BUILD YOUR FLEET



PERFORMANCE

MAX WORKING HEIGHT
65 ft 7 in.

MAX PLATFORM HEIGHT
60 ft 7 in.

HORIZONTAL OUTREACH
39 ft 9 in.

PLATFORM CAPACITY
500 lb, Unrestricted

UP & OVER CLEARANCE
26 ft 7 in.

INSULATION
46 kV Cat E

PACKAGE HIGHLIGHTS

- 46 kV Cat E insulated articulating boom (***not suitable for glove work***)
- 360° continuous swing with zero tail swing
- 130° jib articulation, +70° / -60°
- 180° hydraulic platform rotation
- 500 lb unrestricted platform capacity
- 45% gradeability with 4WD
- 4.25 mph drive speed, 12 in. clearance
- 36 in. × 96 in. insulated basket

MACHINE DIMENSIONS

MACHINE WIDTH **8 ft 2 in.**	MACHINE HEIGHT **8 ft 4 in.**	GROUND CLEARANCE **12 in.**	BASE WEIGHT **22,691 lb**
MACHINE LENGTH **28 ft 11.5 in.**	WHEELBASE **8 ft**	TAILSWING **Zero**	CONFIGURED **22,600-26,200 lb**

WHAT THE I MEANS

A ARTICULATING

Up-and-over access around structures, equipment and energized work areas.

J JIB

130° of articulation at the end of the boom for final basket positioning.

I INSULATED

46 kV Cat E dielectric-rated configuration built for utility applications.

Base-machine data reflects the JLG 600AJ specification sheet; insulated configuration may affect final weight and dimensions. Current dielectric test documentation and the intended work practice must be confirmed before use.

NEW EQUIPMENT PACKAGE PRICE

Tax, title and delivery additional where applicable.

CALL FOR PRICE