THE CONNER GROUP

DPM2-52DP

DUR-A-LIFT PERSONNEL BUCKET

MAX. WORKING HEIGHT*	PLATFORM HEIGHT	MAX. SIDE REACH	BASKET CAPACITY
59 ft	52 ft	31 ft 6 in	600 lb

***59-ft maximum working height requires the optional 22-in basket elevator.**



Manufacturer reference build photo; chassis and installed options vary.

PERSONNEL CONFIGURATION

- Double-person telescopic articulating lift
- 24 x 42-in basket; aluminum or fiberglass
- 180-degree basket rotation
- Hydraulic basket leveling
- Proportional controls; lower override
- Engine start/stop from basket
- Basket accessible from ground

INSULATION & OPTIONS

DPM2: insulated, Category C or D.
DPM2S: non-insulated alternative.
Basket elevator, outriggers, liners, tool circuits and DC backup are options.

MODEL SPECIFICATIONS

Height to platform bottom	52 ft
Maximum working height*	59 ft
Side reach	31 ft 6 in
Approx. stowed height	11 ft 8 in
Approx. lift weight	4,400 lb
Articulating arm travel	0 to 75 deg
Main boom travel	-30 to 75 deg
Extension travel	120 in
Basket capacity (DP)	600 lb
Basket rotation	180 degrees

Confirm rental-unit configuration and insulation rating. Specifications may vary with chassis and options.
Source: dur-a-lift.com/products/dpm2-dp-series/ and manufacturer DPM2 specifications table.